# GENERATION BRANDS, LLC

# TEST REPORT

**SCOPE OF WORK**
Electrical and Photometric tests as required to the IESNA test standard.

**MODEL NUMBER**
700FJALIWS-LEDS930

**REPORT NUMBER**
103643585CHI-097

**ISSUE DATE**
May 29, 2019

**REVISION DATE**
None

**DOCUMENT CONTROL NUMBER**
TBD


545 E. Algonquin Rd
Arlington Heights, IL 60005
Telephone: (847) 439-5667
www.intertek.com

**REPORT NO.:103643585CHI-097**

**TEST REPORT** **REPORT DATE: May 29, 2019**

TEST OF ONE LED PENDANT

MODEL NO. 700FJALIWS-LEDS930

RENDERED TO:

GENERATION BRANDS, LLC
7400 LINDER AVE.
SKOKIE, IL 60077

**AUTHORIZATION**
The testing performed was authorized by signed quote number Qu-00912313-2 .

**STANDARDS USED**
IESNA LM-79 - 2008: Electrical and Photometric Measurements of Solid State Lighting
ANSI NEMA ANSLG C78.377: 2015: Specifications of the Chromaticity of Solid State Lighting Products

**DESCRIPTION OF SAMPLE**
The client submitted one production sample of model number 700FJALIWS-LEDS930. The sample was received by Intertek on May 15, 2019 in undamaged condition and one sample was tested as received. The sample designation was AH05152019114818-097.

**DATE OF TESTS**
May 29, 2019 through May 31, 2019.

545 E. Algonquin Rd
Arlington Heights, IL 60005
Telephone: (847) 439-5667
www.intertek.com

**REPORT NO.:103643585CHI-097**

**TEST REPORT**

**REPORT DATE: May 29, 2019**

## SUMMARY

| | |
|---|---|
| **MODEL NO:** | 700FJALIWS-LEDS930 |
| **DESCRIPTION:** | LED Pendant |

| CRITERIA | RESULTS | |
|---|---|---|
| | INTEGRATING SPHERE | GONIOPHOTOMETER |
| Lumen Output (lumens) | 362.6 | 357.1 |
| Input Power (W) @ 12 (VAC) | 7.13 | 7.14 |
| Lumen Efficacy (lm/W) | 50.9 | 50.0 |
| Input Power Factor @ 12 (VAC) | 0.926 | 0.919 |

| CRITERIA | RESULTS |
|---|---|
| Input Current ATHD (%) @ 12 (VAC) | 37.16 |
| Correlated Color Temperature (K) | 2953 |
| Color Rendering Index - Ra | 94.1 |
| Color Rendering - R9 | 96.1 |
| DUV | 0.0007 |
| Chromaticity Coordinate (x) | 0.442 |
| Chromaticity Coordinate (y) | 0.408 |
| Chromaticity Coordinate (u') | 0.252 |
| Chromaticity Coordinate (v') | 0.524 |

545 E. Algonquin Rd
Arlington Heights, IL 60005
Telephone: (847) 439-5667
www.intertek.com



## EQUIPMENT LIST

| EQUIPMENT USED | MODEL NO. | CONTROL NO. | LAST CAL DATE | CAL DUE DATE |
|---|---|---|---|---|
| Yokogawa Power Meter | WT210 | 146919 | 7/9/2018 | 7/9/2019 |
| Omega Newport Thermometer | DPI8-C24 | 146920 | 10/4/2018 | 10/4/2019 |
| LSI High Speed Mirror Goniometer | 6440T | 146928 | VBU | VBU |
| Newport Thermohygrometer | iServer | 146957 | 12/11/2018 | 12/11/2019 |
| Pacific, AC power supply | 118-ACX | CHI0358 | VBU | VBU |
| Labsphere 2M Sphere & Spectroradiometer | CDS1100 | 146137 | VBU | VBU |
| Elgar AC Power Supply | CW1251M | 146113 | VBU | VBU |
| Sorenson DC Power Supply | XFR150-8 | 146847 | VBU | VBU |
| Yokogawa Power Analyzer | WT1600 | 146767 | 4/3/2019 | 4/3/2020 |
| Omega Temperature | MDSi8 | 146873 | 7/10/2018 | 7/10/2019 |
| Newport Thermohygrometer | iTHX-M | 146961 | 7/23/2018 | 7/23/2019 |

## TEST METHODS

### SEASONING IN SAMPLE ORIENTATION - LED PRODUCTS

No seasoning was performed in accordance with IESNA LM-79.

### PHOTOMETRIC AND ELECTRICAL MEASUREMENTS - INTEGRATING SPHERE METHOD

A Spectroradiometer and integrating sphere was used to measure correlated color temperature, chromaticity coordinates, and the color rendering index for each SSL unit.

Ambient temperature was measured at a position inside the sphere. Each SSL unit was operated on the client provided driver at the rated input voltage in its designated orientation. Each SSL unit was allowed to stabilize for at least thirty minutes before measurements were made. Stabilization procedures to LM-79 were followed. Electrical measurements including voltage, current, and power were measured using a power analyzer.

The calibration of the sphere photometer-spectroradiometer system is traceable to the National Institute of Standards and Technology.

### PHOTOMETRIC AND ELECTRICAL MEASUREMENTS - DISTRIBUTION METHOD

A Type C Mirror Goniometer was used to measure the intensity (candelas) at each angle of distribution for the SSL sample.

Ambient temperature was measured equal to the height of the sample mounted on the goniometer equipment. The SSL sample was operated on the client provided driver at rated input volts in its designated orientation. The SSL sample was allowed to stabilize for at least thirty minutes before measurements were made. Stabilization procedures to LM-79 were followed. Electrical measurements including voltage, current, and power were measured using a power analyzer.

545 E. Algonquin Rd
Arlington Heights, IL 60005
Telephone: (847) 439-5667
www.intertek.com

**REPORT NO.:103643585CHI-097**
**REPORT DATE: May 29, 2019**

**TEST REPORT**

## RESULTS OF TESTS

### PHOTOMETRIC AND ELECTRICAL MEASUREMENTS - DISTRIBUTION METHOD (25°C +/- 1°C)

| INTERTEK CONTROL NO. | BASE POSITION | INPUT VOLTAGE (VAC) | INPUT CURRENT (mA) | INPUT POWER (W) | INPUT POWER FACTOR | LIGHT OUTPUT (lm) | LUMEN EFFICACY (lm/W) |
|---|---|---|---|---|---|---|---|
| AH05152019114818-097 | Base Up | 12.0 | 648.3 | 7.14 | 0.919 | 357.1 | 50.0 |

### INTENSITY SUMMARY - CANDELAS

| Angle | 0 | 22.5 | 45 | 67.5 | 90 |
|---|---|---|---|---|---|
| 0 | 124 | 124 | 124 | 124 | 124 |
| 5 | 124 | 122 | 122 | 123 | 123 |
| 10 | 120 | 118 | 118 | 118 | 117 |
| 15 | 118 | 113 | 113 | 112 | 112 |
| 20 | 109 | 103 | 103 | 103 | 103 |
| 25 | 85 | 82 | 85 | 88 | 88 |
| 30 | 60 | 58 | 61 | 63 | 64 |
| 35 | 51 | 51 | 51 | 51 | 51 |
| 40 | 48 | 47 | 46 | 43 | 42 |
| 45 | 39 | 38 | 38 | 37 | 36 |
| 50 | 37 | 36 | 36 | 35 | 34 |
| 55 | 34 | 34 | 33 | 33 | 32 |
| 60 | 31 | 31 | 30 | 30 | 30 |
| 65 | 31 | 30 | 30 | 30 | 29 |
| 70 | 30 | 30 | 30 | 29 | 29 |
| 75 | 29 | 29 | 28 | 28 | 28 |
| 80 | 28 | 27 | 27 | 26 | 26 |
| 85 | 26 | 25 | 25 | 25 | 24 |
| 90 | 24 | 24 | 23 | 23 | 23 |
| 95 | 23 | 23 | 23 | 22 | 22 |
| 100 | 22 | 22 | 22 | 22 | 22 |
| 105 | 22 | 21 | 21 | 21 | 21 |
| 110 | 21 | 20 | 20 | 20 | 20 |
| 115 | 19 | 19 | 19 | 19 | 19 |
| 120 | 18 | 18 | 18 | 18 | 18 |
| 125 | 17 | 16 | 16 | 16 | 16 |
| 130 | 16 | 15 | 15 | 15 | 15 |
| 135 | 14 | 14 | 14 | 14 | 14 |
| 140 | 13 | 13 | 12 | 12 | 12 |
| 145 | 12 | 11 | 11 | 11 | 11 |
| 150 | 10 | 10 | 10 | 10 | 10 |
| 155 | 9 | 9 | 8 | 9 | 9 |
| 160 | 7 | 6 | 5 | 6 | 7 |
| 165 | 4 | 3 | 1 | 2 | 3 |



545 E. Algonquin Rd
Arlington Heights, IL 60005
Telephone: (847) 439-5667
www.intertek.com

**REPORT NO.:103643585CHI-097**

**TEST REPORT** **REPORT DATE: May 29, 2019**

## RESULTS OF TESTS

### PHOTOMETRIC AND ELECTRICAL MEASUREMENTS - DISTRIBUTION METHOD (25°C +/- 1°C)

**MOUNTING HEIGHT: 10ft**

**ILLUMINANCE - CONE OF LIGHT**


**ISOILLUMINATION PLOT**




**ZONAL LUMEN SUMMARY AND PERCENTAGES**

| ZONE | LUMENS | % LUMINAIRE |
|---|---|---|
| 0-30 | 81.5 | 22.8 |
| 0-40 | 113.4 | 31.8 |
| 0-60 | 170.7 | 47.8 |
| 60-90 | 84.9 | 23.8 |
| 70-100 | 80.1 | 22.4 |
| 90-120 | 64.5 | 18.1 |
| 0-90 | 255.6 | 71.6 |
| 90-180 | 101.4 | 28.4 |
| 0-180 | 357.1 | 100.0 |

| ZONE | LUMENS | % LUMINAIRE |
|---|---|---|
| 0-10 | 11.5 | 3.2 |
| 10-20 | 31.6 | 8.8 |
| 20-30 | 38.4 | 10.8 |
| 30-40 | 31.9 | 8.9 |
| 40-50 | 28.6 | 8.0 |
| 50-60 | 28.6 | 8.0 |
| 60-70 | 29.0 | 8.1 |
| 70-80 | 29.3 | 8.2 |
| 80-90 | 26.6 | 7.4 |
| 90-100 | 24.2 | 6.8 |
| 100-110 | 21.9 | 6.1 |
| 110-120 | 18.5 | 5.2 |
| 120-130 | 14.5 | 4.1 |
| 130-140 | 10.6 | 3.0 |
| 140-150 | 7.1 | 2.0 |
| 150-160 | 3.9 | 1.1 |
| 160-170 | 0.8 | 0.2 |

545 E. Algonquin Rd
Arlington Heights, IL 60005
Telephone: (847) 439-5667
www.intertek.com

**REPORT NO.:103643585CHI-097**
**REPORT DATE: May 29, 2019**

**TEST REPORT**

**RESULTS OF TESTS**

**PHOTOMETRIC AND ELECTRICAL MEASUREMENTS - INTEGRATING SPHERE METHOD (25°C +/- 1°C)**

| INTERTEK CONTROL NO. | BASE POSITION | INPUT VOLTAGE (VAC) | INPUT CURRENT (mA) | INPUT POWER (W) | INPUT POWER FACTOR | INPUT CURRENT ATHD (%) |
|---|---|---|---|---|---|---|
| AH05152019114818-097 | Base Up | 12.00 | 641.70 | 7.13 | 0.926 | 37.16 |

| LIGHT OUTPUT (lm) | LUMEN EFFICACY (lm/W) | CORRELATED COLOR TEMPERATURE - CCT (K) | CRI - Ra | CRI - R9 | DUV |
|---|---|---|---|---|---|
| 362.6 | 50.9 | 2953 | 94.1 | 96.1 | 0.0007 |

| CIE 1931 CHROMATICITY COORDINATE (x) | CIE 1931 CHROMATICITY COORDINATE (y) | CIE 1976 CHROMATICITY COORDINATE (u') | CIE 1976 CHROMATICITY COORDINATE (v') |
|---|---|---|---|
| 0.442 | 0.408 | 0.252 | 0.524 |



545 E. Algonquin Rd
Arlington Heights, IL 60005
Telephone: (847) 439-5667
www.intertek.com

**REPORT NO.:103643585CHI-097**

**TEST REPORT** **REPORT DATE: May 29, 2019**

## RESULTS OF TESTS

### PHOTOMETRIC AND ELECTRICAL MEASUREMENTS - INTEGRATING SPHERE METHOD (25°C +/- 1°C)

| SPECTRAL DISTRIBUTION OVER VISIBLE WAVELENGTHS* | | | | | | | |
|---|---|---|---|---|---|---|---|
| nm | mW/nm | nm | mW/nm | nm | mW/nm | nm | mW/nm |
| 350 | 0.045 | 460 | 1.532 | 570 | 4.495 | 680 | 4.968 |
| 355 | 0.050 | 465 | 1.788 | 575 | 4.640 | 685 | 4.536 |
| 360 | 0.048 | 470 | 2.068 | 580 | 4.898 | 690 | 4.124 |
| 365 | 0.045 | 475 | 2.385 | 585 | 4.954 | 695 | 3.724 |
| 370 | 0.047 | 480 | 2.723 | 590 | 5.366 | 700 | 3.333 |
| 375 | 0.048 | 485 | 3.053 | 595 | 5.782 | 705 | 2.970 |
| 380 | 0.055 | 490 | 3.335 | 600 | 6.200 | 710 | 2.634 |
| 385 | 0.076 | 495 | 3.537 | 605 | 6.585 | 715 | 2.333 |
| 390 | 0.112 | 500 | 3.678 | 610 | 6.912 | 720 | 2.062 |
| 395 | 0.198 | 505 | 3.736 | 615 | 7.227 | 725 | 1.809 |
| 400 | 0.523 | 510 | 3.762 | 620 | 7.456 | 730 | 1.576 |
| 405 | 1.521 | 515 | 3.782 | 625 | 7.614 | 735 | 1.346 |
| 410 | 3.183 | 520 | 3.796 | 630 | 7.677 | 740 | 1.152 |
| 415 | 4.182 | 525 | 3.802 | 635 | 7.683 | 745 | 1.005 |
| 420 | 2.960 | 530 | 3.861 | 640 | 7.608 | 750 | 0.880 |
| 425 | 1.709 | 535 | 3.961 | 645 | 7.446 | 755 | 0.772 |
| 430 | 1.108 | 540 | 4.087 | 650 | 7.215 | 760 | 0.674 |
| 435 | 0.818 | 545 | 4.180 | 655 | 6.932 | 765 | 0.584 |
| 440 | 0.811 | 550 | 4.285 | 660 | 6.607 | 770 | 0.503 |
| 445 | 0.932 | 555 | 4.392 | 665 | 6.229 | 775 | 0.434 |
| 450 | 1.106 | 560 | 4.500 | 670 | 5.816 | 780 | 0.375 |
| 455 | 1.311 | 565 | 4.587 | 675 | 5.403 | | |

*Without correction of sample absorption.




**End Of Test Results**

545 E. Algonquin Rd
Arlington Heights, IL 60005
Telephone: (847) 439-5667
www.intertek.com

**REPORT NO.:103643585CHI-097**
**REPORT DATE: May 29, 2019**

**TEST REPORT**

**PICTURES**

**CONCLUSION**

The results tabulated in this report are representative of the actual test samples submitted for this report only. The data is provided to the client for further evaluation. Compliance to the referenced specification requirements was not determined in this report.

In Charge Of Tests:

Tess Gallagher
Engineer
Lighting Division

Report Reviewed By:

Timothy Quigley
Project Engineer
Lighting Division

Attachments: IES File

**REVISION HISTORY**

| JOB NUMBER | DATE OF REVISION | PROJECT HANDLER | REVIEWED BY | REVISION NOTE |
|---|---|---|---|---|
| None | | | | |